



- NOTES:**
- THESE PLANS ARE NOT BASED ON FIELD RUN SURVEY. LOCATION OF EXISTING AND PROPOSED FEATURES SHOWN ON PLANS ARE APPROXIMATE.
  - SAW CUTTING FOR MILLING AND RESURFACING SHALL BE INCIDENTAL TO THE ASPHALT PAVING ITEMS.
  - EX. SIGNS SHALL BE RELOCATED AT A MINIMUM OF 24 INCHES FROM THE FACE OF CURB TO EDGE OF SIGN FACE.
  - ALL DIMENSIONS FROM THE CROSSWALK IS MEASURED TO THE FACE OF CURB OF THE INTERSECTING STREET.
  - CONTRACTOR SHALL NOTIFY TOWN ONE WEEK PRIOR TO WORK
  - CONTRACTOR SHALL NOTIFY PROPERTY OWNER(S) THREE DAYS PRIOR TO WORK

APPROXIMATE SELECTED QUANTITIES ON THIS SHEET

DESCRIPTION	UNITS	QTY
ADJUST MANHOLE TO GRADE	EA	1
CONCRETE SIDEWALK	SF	240
TURFGRASS ESTABLISHMENT	SY	18
TOPSOILING - 2 INCH	SY	18
CLASS 2 EXCAVATION	CY	3
4 INCH GRADED AGGREGATE SUBBASE (GASB) COURSE	SY	27

LEGEND

- NEW CONCRETE SIDEWALK
- (A)** CONCRETE SIDEWALK - 5 FOOT WIDE
- (B)** 2" TOPSOIL AND TURFGRASS EST.



SCALE: 1" = 40'

**Pennoni**  
**PENNONI ASSOCIATES INC.**  
 351 W Camden Street, Suite 200  
 Baltimore, MD 21201  
 T 410.878.9550  
 F 410.878.9551

*PROFESSIONAL CERTIFICATION*

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.

LICENSE NO.: 33919  
 EXPIRATION DATE: 01/25/2025

04/26/23	ADDENDUM NO. 1	DK
05/04/23	ADDENDUM NO. 2	DK
DATE	NO.	REVISIONS

**RIVERDALE PARK**  
**ROAD IMPROVEMENT PROGRAM - FY2023**  
 TOWN OF RIVERDALE PARK  
 PRINCE GEORGE'S COUNTY, MD

5014 SHERIDAN ST

5008 QUEENSBURY ROAD  
 RIVERDALE PARK, MD 20737  
 DEPARTMENT OF PUBLIC WORKS

CONTRACT NO.	DWP 2023-003
DATE	04/13/2023
DRAWING SCALE	1" = 40'
DRAWN BY	DK
APPROVED BY	AM / EH
DWG. NO.	PS-14 OF 34
<b>ROADWAY PLAN</b>	
SHEET 20 OF 40	